

PUMPTRACK CONCEPT OPTION [02]

PUMPTRACK INFRASTRUCTURE: [00]



- 1. +1.2m(H) take-off platform arbor structure over
- 2. +350(H) double pump entry point
- 3. +500(H) quadruple pump into long loop
- 4. +350(H) single pump into +1.0m(H) berm
- 5. +1.5m(H) long wall-ride
- 6. +500(H) triple pump out of wall-ride
- +750(H) bowl
- 8. +300(H) +900(H) 5 x roll-overs
- 9. +550(H) single pump into berm
- 10. +1.0m(H) berm
- 11. +550(H) double pump out of berm
- 12. +500(H) +900(H) deep bowls with spines
- 13. +450(H) double pump into return loop
- 14. +650(H) double pump shortcut into big bern loop
- 15. +750(H) triple pump into tight whip berm
- 16. +1.2m(H) tight whip berm
- 17. +650(H) double pump out of whip bern loop
- 18. +450(H) double pump return to take-off platform

LANDSCAPE INFRASTRUCTURE



- 1. Proposed formal entry node and signage
- 2. Existing pathway alignment to be upgraded
- Proposed natural refuge area with shade trees
- 4. Proposed shipping container "Cantina" food outlet
- 5. Proposed communal seating and gathering space to cantina with shade trees, tables, chairs, bins, drinking fountains and festoon lighting,
- 6. Proposed connection pathways
- 7. Proposed feature mural wall to replace existing memorial mural
- Proposed spectators area and gathering space
- 9. Proposed leveled turf area
- 10. Proposed basketball half courts with backing nets
- 11. Colourful Arbor structure

3D CONCEPT VIEWS: OVERALL PUMPTRACK PERSPECTIVE 02 -

